

1 040435

6 -

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,959-0000

NW SE SE, SEC. 33, T 34 S, R 12 W/E

990 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3906

Lease Name Vogel Well # 4

Operator: Robert McCandless

County Barber 157.30

Name & Address 719 Illinois

Well Total Depth 4840 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 412

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 p.m. Day: 29 Month: 6 Year: 19 90

Plugging proposal received from Robert McCandless

(company name) Robert McCandless (phone) 316-672-6681

were: 4 1/2" at 4839' PBD 4839' Perfs at 4760-70'

1st plug sand back to 4710' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls and 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 29 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4710' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 200 lbs. hulls and 150 sx cement.

Maximum pressure 350 psi and shut in 250 psi.

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1990

7-6-90

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3560

CONSERVATION DIVISION
Wichita, Kansas

(if additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 7-9-90

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 28554