

2-18-88

149
R

1 040059

API NUMBER 15- 007-20,868-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SW, SEC. 33, T 34 S, R 12 W/E
2310 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Lease Name Vogel Well # A-5

Operator: Farrar Pump and Supply Company
Name & Address

County Barber 158.24

Junction 160 and 281

Well Total Depth 4869 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 330

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 18 Month: 2 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4869' PBTD 4868' Perfs at 4808-18'

1st plug sand back from 4868-4760' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls and 125 sx econolite cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:30 a.m. Day: 18 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back from 4868-4760' and dumped 4 sx cement on

top of sand through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls ahead of cement and 200

lbs. hulls in with first part of cement and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1988
2-24-88
CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 250 psi and shut in 150 psi.

Remarks: Used Thrifty Mix cement by B.J. Titan. Recovered 3500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 2-26-88

INV. NO. 19920