

2-18-88

146

R

1 040058

API NUMBER 15-007-21,146-0000

To:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW SE, SEC. 33, T 34 S, R 12 W 12

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Lease Name Vogel Well # A-7

Operator: Farrar Pump and Supply Company
Name &

County Barber 157.63

Address Junction 160 and 281

Well Total Depth 4850 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 333

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ O&A ☐

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 18 Month: 2 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-3763

were: 4 1/2" at 4849' PBT 4849' Perfs at 4788-98'

1st plug sand back from 4849' to 4738' and dump 4 sx cement on top of sand through
bailer,

2nd plug pump 5 sx hulls and 125 sx econolite cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 10:45 a.m. Day: 18 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back from 4849-4738' and dumped 4 sx cement on top
of sand through bailer,2nd plug pumped down 10 3/4" with 300 lbs. hulls ahead of cement and 200 lbs. hulls in
with first of cement and 125 sx cement.

STATE CORPORATION COMMISSION

FEB 24 1988

2-24-88

CONSERVATION DIVISION

Wichita, Kansas

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used Thrifty Mix cement by B.J. Titan. Recovered 3500' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed

Steve Pfeifer
(TECHNICIAN)

DATE 2-26-88

WV. NO. 19919