

2-18-88

145  
R

1 040057

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,145-0000  
NW NW SW, SEC. 33, T 34 S, R 12 W  
2310 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3399  
Operator: Farrar Pump and Supply Company  
Name & Address Junction 160 & 281  
Medicine Lodge, KS 67104

Lease Name Vogel Well # A-6  
County Barber 158.11  
Well Total Depth 4865 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 327

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:15 p.m. Day: 18 Month: 2 Year: 19 88

Plugging proposal received from Elmo Morgenstern  
(company name) Clarke Corporation (phone) 316-886-5665  
were: 4 1/2" at 4864' PBD 4864' Perfs at 4812-20'

1st plug sand back from 4864-4760' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 5 sx hulls and 125 sx econolite.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 p.m. Day: 18 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back from 4864-4760' and dumped 4 sx cement on top  
of sand through bailer,

2nd plug pumped down 10 3/4" with 300 lbs. hulls ahead of cement and 200 lbs. of hulls  
in with first of cement and 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used Thrifty Mix cement by B.J. Titan. Recovered 3500' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Stephen J. Pfeifer  
(TECHNICIAN)

DATE 2-26-88

INV. NO. 19921