

To: 1 040675  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

7-29 API NUMBER 15- 007-20,855-0000 226 R

NW SE SW, SEC. 33, T. 34 S, R 12 W/E  
990 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552  
Operator: Gore Oil Company  
Name & Address P.O. Box 2757  
Wichita, KS 67201-2757

Lease Name Graves A Well # 2  
County Barber 159.25  
Well Total Depth 4900 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1 p.m. Day: 29 Month: 7 Year: 19 92  
Plugging proposal received from Scott Scheuerman  
(company name) Gore Oil Company (phone) 316-263-3535

work: 4 1/2" at 4899' w/275 sx cement, PBTD 4850', Perfs at 4834-44'  
1st plug sand back to 4780' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 2 p.m. Day: 29 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4780' and dumped 4 sx cement on top of sand  
bridge through bailer,  
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.  
hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Maximum pressure 200 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2600' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
DATE 8-10-92  
INV. NO. 35910

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 4 1992  
8-04-92  
Conservation Division  
Wichita, Kansas  
Signed Steph...  
(TECHNICIAN)