

To: 1 040674
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-29 API NUMBER 15- 007-20.759-000 227 R

SE SW, SEC. 33, T 34 S, R 12 W/EX
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Graves A Well # 1

Operator: Gore Oil Company

County Barber

Name & Address P.O. Box 2757

Well Total Depth 4878 158.53 feet

Wichita, KS 67201-2757

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12 p.m. Day: 29 Month: 7 Year: 19 92

Plugging proposal received from Scott Scheuerman

(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4877' w/175 sx cement, PBD 4869', Perfs at 4813-21'

1st plug sand back to 4770' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 29 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4770' and dumped 4 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 300 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3450' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 8-10-92

CV. NO. 35911

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

8-4-92
CONSERVATION DIVISION
Wichita, Kansas