

To: 1 040677
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-29 API NUMBER 15- Docket #D-20,083 229 R

NW SW SW, SEC. 33, T. 34 S, R. 12 W/E
990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552
Operator: Gore Oil Company
Name & Address: P.O. Box 2757
Wichita, KS 67201-2757

Lease Name Graves A Well # 4
County Barber 158.08
Well Total Depth 4864 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 415

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:45 a.m. Day: 29 Month: 7 Year: 19 92
Plugging proposal received from Scott Scheuerman
(company name) Gore Oil Company (phone) 316-263-3535

were: 4 1/2" at 4863' w/225 sx cement, PBTD 4700', Perfs at 4366-4434'
1st plug sand back to 4320' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 10 3/4" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, release 10 3/4" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 11:30 a.m. Day: 29 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4316' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 125 sx cement.
Maximum pressure 150 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION
8-4-92
AUG 4 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 8-10-92
NO. 35913

Signed Stephen J. Pfeifer
(TECHNICIAN)