

To: 1 040501  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-25  
API NUMBER 15- 007-21,147-0000 176p  
NW SE SE, SEC. 33, T 34 S, R 12 W/E  
990 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3906

Lease Name Vogel Well # 8

Operator: Robert McCandless

County Barber 156.84

Name & Address 719 Illinois

Well Total Depth 4826 feet

Pratt, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 318

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12 p.m. Day: 25 Month: 1 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4813' w/225 sx cement, Perfs at 4770-80'

1st plug sand back to 4690' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

STATE CORPORATION COMMISSION

1-31-91  
JAN 31 1991

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN) CONSERVATION DIVISION  
Wichita, Kansas

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 25 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4690' and dumped 4 sx cement on top of

sand bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 125 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

Surface pipe plated with collar welded in to pump through.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3105' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED (Do not observe this plugging.)

Signed Steve Pfeifer (TECHNICIAN)

DATE FEB 12 1991

INV. NO. 30697