

1091059

TO: STATE CORPORATION COMMISSION

API NUMBER 15-007-21,468-0000  
C NE NE SEC. 28, T 34 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME JENKINS WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER 156.98

OPERATOR LICENSE # 5254

WELL TOTAL DEPTH 4830 FEET

OPERATOR: MIDCO EXPLORATION, INC. PRODUCTION CSG: SIZE 4 1/2" @ 4833' WITH 150 SX

NAME AND 414 PLAZA DRIVE, SUITE 204 SURFACE CASING: SIZE 8 5/8" @ 1080' WITH 350 SX

ADDRESS WESTMONT, IL 60559 CONDUCTOR CSG: SIZE " @ '

ABANDONED OIL WELL    GAS WELL X INPUT WELL    SWD WELL    D/A   

OTHER WELL AS HEREINAFTER INDICATED   

PLUGGING CONTRACTOR SARGENT'S CASING PULLING SERVICE LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67905-0506

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 15 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DAVE MAYFIELD

(COMPANY NAME) SARGENT'S CASING PULLING SERVICE (PHONE) 316-624-7455

WERE: PERFS AT 4573-76

1ST PLUG PUMP 20 SX CEMENT AT 4500'. 2ND PLUG PUMP 50 SX CEMENT AT 1100'. 3RD PLUG PUMP 40 SX CEMENT AT 400'. 5TH PLUG PUMP 10 SX CEMENT AT 40-0'.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART    NONE   

OPERATIONS COMPLETED: HOUR: 12:30 PM DAY: 15 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT   

1ST PLUG SET CIBP @ 4520' WITH 2 SX CEMENT ON TOP. 2ND PLUG PULL CASING TO 1100'. LOAD HOLE WITH MUD. SPOT 50 SX CEMENT. 3RD PLUG PULL TO 400' SPOT 40 SX CEMENT. 4TH PLUG PULL TO 40' SPOT 10 SX CEMENT. STAYED FULL.

RECEIVED  
STATE CORPORATION COMMISSION

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 3800' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

JUN 19 2000  
6-19-00

I (DID)

OBSERVE THIS PLUGGING.

INVOICED

DATE 6/21/00

SIGNED

(TECHNICIAN)

FORM CP-2/3

INV. NO. 61885

CONSERVATION DIVISION  
WICHITA, KANSAS