

1 050753

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,041-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: TXO Production Corp.
Name & Address: 155 North Market, Suite 1000
Wichita, KS 67202

20' N E/2 NW, SEC. 28, T 34 S, R 14 W/4
3980 feet from S section line
3300 feet from E section line

Lease Name EWB Well # 1

County Barber 159.93

Well Total Depth 4921 feet

Conductor Pipe: Size 16" feet 40

Surface Casing: Size 8 5/8 feet 1086

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Clarke Oilfield Services License Number 5105

Address 107 Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:00 pm Day: 24 Month: January Year: 19 86

Plugging proposal received from Jerry Pritchert

(company name) TXO (phone) 316-269-7600

were: 4 1/2" at 4919' PBT 4877' Perfs at 4849-59'; 4847-59'

1st plug sand back to 4800' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45 pm Day: 24 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1986
30-86
CONSERVATION DIVISION

Maximum pressure 825 psi and shut in 600 psi

Remarks: Recovered 3795' 4 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan
(if additional description is necessary, use BACK of this form.)

INVOICED
(if not) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE JAN 31 1986

INV. NO. 12224