

To: 1040738
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-9

API NUMBER 15- 007-22,306-0000

SW NE SE, SEC. 28, T 34 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Operator: Marathon Oil Corp.
Name & Address: RR 1, Box 25
Medicine Lodge, KS 67104

1650 feet from S section line

990 feet from E section line

Lease Name Chastel Well # 1

County Barber 169.00

Well Total Depth 5200 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1061

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12 p.m. Day: 9 Month: 2 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3900' w/100 sx cement, PBSD 3900', Perfs at 3775-3778'

1st plug sand back to 3725' and dump .4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper

plug and pump 100' sx cement.

RECEIVED
KANSAS CORPORATION COM.
2-11-93

Plugging Proposal Received by _____

FEB 11 1993
Steve Pfeifer
TECHNICIAN
CONSERVATION DIVISION
WICHITA, KS 67202

Plugging Operations attended by Agent?: All Part _____

Operations Completed: Hour: 12:45 p.m. Day: 9 Month: 2 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3725' and dumped 4 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1250 psi and shut in 800 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

1. (If applicable) observe this plugging.

DATE 2-19-93

WV. NO. 37392

Signed Stephen J. Pfeifer
(TECHNICIAN)