

1 110013

API NUMBER 15- 007-22,104-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NE , SEC. 5 , T 32 S, R 15 ~~WXX~~

3630 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9682

Lease Name Marsh Well # 1-5

Operator: Harry A. Spring

County Barber

Name: Harry A. Spring

Well Total Depth 5398 Arbuckle ^{175.44} feet

Address P. O. Box 1788
Ardmore, OK 73402

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 432

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor H-30, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 7:30 pm Day: 15 Month: December Year: 19 85

Plugging proposal received from E. J. Woody

(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2017'
Anhydrite 1000'

1st plug in the Arbuckle with 50 sx cement if in 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with
15 sx cement Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:00 pm Day: 15 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 5350' with 50 sx cement, 2nd plug at 1000' with 50
sx cement, 3rd plug at 480' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15
sx cement, 7th plug to circulate mouse hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 20 1985

INV. NO. 11681

STATE CORPORATION COMMISSION
Signed

James R. Kapp
(TECHNICIAN)

DEC 20 1985
12-20-85
CONSERVATION DIVISION

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: November, 25, 1985
month day year

API Number 15- 007-22,104-0000

OPERATOR: License # 9682
Name Harry A. Spring
Address P.O. Box 1788
City/State/Zip Ardmore, Oklahoma 73402
Contact Person Harry A. Spring
Phone 405/226-3800

NE, SW, NE, SE (location) Sec. 5, Twp. 32 S, Rge. 15. East West
3630 Ft North from Southeast Corner of Section
1650 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107
Name H-30 Drilling Inc.
City/State Wichita, Kansas

Nearest lease or unit boundary line 990 feet.
County Barber
Lease Name Marsh Well# 1-5
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
Oil Swd Infield Mud Rotary
Gas Inj Prod Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 200 feet
Lowest usable water formation 200
Depth to Bottom of usable water 200 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 425 feet
Conductor pipe if any required none feet
Ground surface elevation 2017 feet MSL.
This Authorization Expires 5-12-86
Approved By 11-12-85 RCH/KOWE

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 5,400' feet
Projected Formation at TD Arbuckle
Expected Producing Formations Viola, Topeka, Douglas.

Signature of Operator or Agent *H.A. Spring* Title OWNER
11-7-85
Form C-1 4/84

mov'd 12-6-85 - 8/8 - 425
60/40 Res

PUSHER	E.T. Woods
TD	5398 FORMATION Arbuckle
SURFACE PIPE	5 7/8 @ 432
ANHYDRITE	1000 ELEVATION 2017
STARTING TIME & DATE	
COMPLETION TIME DATE	10:00 pm 12/15/85
1st PLUG @	5350 FT. WI 50 SX
2nd PLUG @	1000 FT. WI 50 SX
3rd PLUG @	480 FT. WI 50 SX
4th PLUG @	40 FT. WI 50 SX
RAT HOLE CIRCULATED WI	15 SX
MOUSE HOLE CIRCULATED WI	19 SX
WATER WELL PLUGGED WI	SX
CEMENT COMPANY	B T Titan
TECHNICIAN	Jeff Dick
	Cur 10 min. wind mud.
	1st Plug - Arb 50 SX
	2nd Plug - Arb 50 SX
	3rd - 30' out of well 50 SX
	4th - 40-5 B.S.F. - 10 SX
	RAT 15
	M. 15
	60/40 Res 69% Gal

RECEIVED
12-20-85
CONSERVATION DIVISION

DEC 27