

1-3 40 R

To: 1 040387  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-22,281-0000

C N/2 NW, SEC. 3, T 32 S, R 15 W/4

4620 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532

Lease Name Ted Alexander Well # 1-3

Operator: CMX, Inc.

County Barber 154.80

Name & Address 1026 Union Center Building

Well Total Depth 4763 feet

Wichita, KS 67202

Conductor Pipe: Size 10 3/4 feet 380

Surface Casing: Size 8 5/8 feet 1550

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A  X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Company License Number 5929

Address 310 West Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 11 p.m. Day: 14 Month: 12 Year: 19 89

Plugging proposal received from John Armbruster

(company name) Duke Drilling Company (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 700'  
1st plug at 1580' with 50 sx cement, 2nd plug at 750' with 40 sx cement,  
3rd plug at 410' with 25 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with 10  
sx cement, 7th plug squeeze 100 sx cement between 10 3/4" X 8 5/8".

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  X None

Operations Completed: Hour: 12:30 p.m. Day: 3 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1580' with 50 sx cement,

2nd plug at 750' with 40 sx cement, 3rd plug at 410' with 25 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement,

7th plug pumped 90 sx cement down 10 3/4" & 8 5/8".

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
JAN 5 1990  
1-5-90  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED observe this plugging.

DATE JAN 26 1990

Signed Stephane Pfeifer  
(TECHNICIAN)

INV. NO. 27181  
1-3

FEB 28 1990

FORM MUST BE SIGNED  
 FORM C-1 12/88  
 EFFECTIVE DATE: 12-06-89 State of Kansas  
 NOTICE OF INTENTION TO DRILL  
 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date December 5, 1989  
 month day year  
 C. N/2 NW. Sec. 3. Twp. 32. S, Rg. 15. X East West

OPERATOR: License # 03532  
 Name: CMX, Inc.  
 Address: 1026 Union Center Building  
 City/State/Zip: Wichita, Kansas 67202  
 Contact Person: Douglas H. McGinness, II.  
 Phone: (316) 269-9052

4620 feet from South line of Section  
 3960 feet from East line of Section  
 (Note: Locate well on Section Plat Below)

CONTRACTOR: License # 5929  
 Name: Duke Drilling Company

County: Barber  
 Lease Name: Ted Alexander Well # 1-3  
 Field Name: Ronald

Well Drilled For: Well Class: Type Equipment:  
 ... Oil ... Inj ... X Infield ... X Mud Rotary  
 ... Gas ... Storage ... Pool Ext. ... Air Rotary  
 ... OAWD ... Disposal ... Wildcat ... Cable  
 ... Seismic; ... # of Holes

Is this a Prorated Field? ... yes X no  
 Target Formation(s): Mississippi  
 Nearest lease or unit boundary: 660  
 Ground Surface Elevation: 1881 feet MSL  
 Domestic well within 330 feet: ... yes X no  
 Municipal well within one mile: ... yes X no  
 Depth to bottom of fresh water: 180'  
 Depth to bottom of usable water: 180'  
 Surface Pipe by Alternate: X 1 ... 2  
 Length of Surface Pipe Planned to be set: 360'  
 Length of Conductor pipe required: None  
 Projected Total Depth: 4800'  
 Formation at Total Depth: Archuckle  
 Water Source for Drilling Operations:  
 ... well X farm pond ... other

If OAWD: old well information as follows:  
 Operator: CONSERVATION DIVISION  
 Well Name: Wichita, Kansas  
 Comp. Date: Old Total Depth

Projected Total Depth: 4800'  
 Formation at Total Depth: Archuckle  
 Water Source for Drilling Operations:  
 ... well X farm pond ... other

Directional, Deviated or Horizontal wellbore? ... yes X no  
 If yes, total depth locations:

DWR Permit #: ...  
 Will Cores Be Taken?: ... yes X no  
 If yes proposed zone:

Exp. 6/1/90

200' Alt. T Req.

AFFIDAVIT

*Logline 850-900' attempted 5 gauges @ \$50*

PUSHER Chamberlain

TD 4265 FORMATION 10 ft @ 380 cc

SURFACE PIPE 8-5/8 @ 1552-2000 ft

ANHYDRITE 200 ELEVATION 1400

STARTING TIME & DATE 11:00 PM - 1/24/89

COMPLETION TIME & DATE 12:30 PM - 1-3-89

1st PLUG @ 1580 FT. WI 50 SX

2nd PLUG @ 750 FT. WI 40 SX

3rd PLUG @ 410 FT. WI 25 SX

4th PLUG @ 40 FT. WI 10 SX

RAT HOLE CIRCULATED WI 15 SX

MOUSE HOLE CIRCULATED WI 10 SX  
*pumped 90sx down 10 ft and 85sx*

WATER WELL PLUGGED WI \_\_\_\_\_ SX

CEMENT COMPANY Howell

TECHNICIAN Phaffer

TYPE OF CEMENT 6040 6%

*John called 12-15-89  
 I wanted to plug it  
 11:00 PM - 12:14 AM @ 5/8"  
 @ 12:14 PM - 12:15  
 I told him that I wanted  
 to plug it with 100mg  
 between 10-4 ft  
 so you now needs to contact  
 Doug M. McGinness OR  
 MST*

5280	1650
4950	1320
4620	990
4290	660
3960	330
3630	
3300	
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

Spud date: 12-4-89 Agent: D.G.

- REMEMBER TO:
- File Drill Pit Application (form COP-1) with Intent to Drill;
  - File Completion Form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.