

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-01196-00-00  
Spot: CNESWSE Sec/Twnshp/Rge: 3-32S-15W  
1100 feet from S Section Line, 1500 feet from E Section Line  
Lease/Unit Name: SKINNER D Well Number: 5  
County: BARBER Total Vertical Depth: 4940 feet

Operator License No.: 31142

Conductor Pipe: Size feet:

Op Name: PETROLEUM PROPERTY SERVICES, INC

Surface Casing: Size 8.625

feet: 287

WITH 250 SX CMT

Address: 155 N. MARKET, STE 1010  
WICHITA, KS 67202

Production: Size 5.5

feet: 4940

WITH 75 SX CMT

Liner: Size

feet:

8160.55

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/08/2002 1:15 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: ALAN VRATIL

Company: PPSI

Phone: (316) 265-3351

Proposed  
Plugging  
Method:

SAND TO 4830' & 5 SX CMT. 1ST PLUG AT 900' WITH 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG

WitnessType: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 05/08/2002 2:45 PM

KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 4913'. PERFS AT 4880-4912'. SAND TO 4830' WITH 5 SX CMT ON TOP. 1ST PLUG PUMP 10 SX GEL. PULL TO 900' AND SPOT 50 SX CMT. 2ND PLUG PULL TO 310' & 50 SX CMT. 3RD PLUG PULL TO 40' & 10 SX CMT. STAYED FULL.

RECEIVED

MAY 15 2002  
5-15-02  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2100' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed

  
(TECHNICIAN)

INVOICE MAY 09 2002

DATE 5-15-02

WV. NO. 2002061782

  
Form