

4-26-88 15-007-01192-0000

1 040090

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion 6/14/58  
NW NE SW, SEC. 2, T 32 S, R 15 W/E  
2310 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Skinner Well # C-3

Operator: National Cooperative Refinery Assoc.  
Name & Address Box 6  
Great Bend, KS 67530

County Barber 160.39  
Well Total Depth 4935 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67530

Company to plug at: Hour: 9 a.m. Day: 26 Month: 4 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4932' PRTD 4917' Perfs at 4844-94' Elevation 1963'KB

1st plug pump 1 sx hulls and 20 sx common cement to 4700';

2nd plug pump 3 sx hulls, 10 sx gel, and 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 02 1988  
5-2-88

Plugging Proposal Received by Steve D... CONSERVATION DIVISION  
(TECHNICIAN) Wichita, Kansas

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:30 a.m. Day: 26 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4790' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, and 10 sx gel, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 350 psi and shut in 200 psi.

Remarks: Used 65/35 Pozmix 8% gel by B.J. Titan. Recovered 4000' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-6-88

INV. NO. 20551

Signed Stephen J. Pfeifer  
(TECHNICIAN)