

To: 1 041167
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-20,406 0000
NW NE SE, SEC. 34, T 34 S, R 14 W/X AUB
2310 feet from S section line
990 feet from E section line

4-22

TECHNICIAN'S PLUGGING REPORT
Operator License # 5447
Operator: OXY USA Inc.
Name:
Address 110 S. Main; Ste. 800
Wichita, KS 67202

Lease Name Baier C Well # 1
County Barber 160.16
Well Total Depth 4928 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 428

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 137, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:30 p.m. Day: 22 Month: 4 Year: 19 96

Plugging proposal received from Alan Vratil
(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 4927' w/250 sx cement, PBTD 4885', Perfs at 4832-76'
1st plug sand back to 4700' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeiffer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 1 p.m. Day: 22 Month: 4 Year: 1996

ACTUAL PLUGGING REPORT 1st plug sanded back to 4748' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Maximum pressure 350 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3100' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
If you do not observe this plugging.

DATE APR 29 1996
INV. NO. 45471

Signed Stephen J. Pfeiffer (TECHNICIAN)

RECEIVED
KANSAS CORP
APR 26 1996

4-26-96