

1 040477

10-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,665-00-00
C NE NE, SEC. 35, T 31 S, R 16 W

TECHNICIAN'S PLUGGING REPORT

4620 feet from S section line
660 feet from E section line

Operator License # 4058

Lease Name Schuette Well # 6

Operator: American Warrior, Inc.

County Comanche 158.66

Name & Address P.O. Box 399

Well Total Depth 4882 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 25 Month: 10 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Gasing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4881' w/170 sx cement, PBT 4800', Top perfs at 4768-72'

1st plug sand back to 4770' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2 p.m. Day: 25 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4700' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 125 sx cement.

Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by RECEIVED Services. Recovered 3300' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging 3 0 1990

INVOICED

DATE 11-5-90

INV. NO. 29819

CONSERVATION DIVISION Wichita, Kansas

Signed Stephen J. Pfeifer (TECHNICIAN)