

RECEIVED
APR 19 2002
4-19-02
KCC WICHITA

15
STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 SOUTH MARKET - ROOM #2078
WICHITA, KANSAS 67202-3802

Form CP-1 (3/92)

Well Plugging Application Form - File One Copy

API#15-007-01196- List for well drilled since 1967, if no API# was issued, use spud or completion.
0000

Well Operator: Petroleum Property Services Inc.

KCC License # 31142 1/03

Address: 155 North Market #1010, Wichita, KS 67202-1824

Phone: 316-265-3351

Lease: SKINNER "D"

Well: 5

SEC: 3

TWN: 32S

RANGE: 15W

Spot Location: APPOX NE SW SE

County: BARBER

1100 Feet from SOUTH Line of Section

1500 Feet from EAST Line of Section

Docket
Number

Oil Well:

X

Gas Well:

D&A:

SWD/EHNR:

Conductor Casing Size:

Set At:

Cemented With:

Sacks

Surface Casing Size: 8 5/8

Set At:

287

Cemented With: 250

Sacks

Production Casing Size: 5 1/2

Set At:

4940

Cemented With: 75

Sacks

List Perforations & Bridge Plugs: PERFORATIONS 4880-4912

Elevation: KB 2019 (G.L./K.B.)

T.D.: 4940

PBTD: 4913

Anhydrite Depth:

(Stone Corral Formation)

Condition of Well: Good:

Poor:

Csg Leak: X

Junk:

Proposed Method of Plugging: ACCORDING TO KCC DIRECTIONS

Is Well Log Attached To This Application As Required? YES

Is ACO-1 Filed? NO

If Not Explain Why? COMPLETED PRIOR TO ACO-1

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND
THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

List Name Of Company Representative Authorized To Be In Charge Of Plugging Operations:

LARRY WALLERT

Mobile Phone: 785-483-1558

Address: P.O. Box 551, Russell, KS 67665

Phone: 785-483-2022

Plugging Contractor: QUALITY WELL SERVICE

KCC License #: 31925 8/02

Address: 401 WEST MAIN, LYONS, KS 67554


Phone: 620-727-3410

Proposed Date & Hour of Plugging (If Known): UNKNOWN, QUALITY WILL CALL KCC

Payment Of The Plugging Fee (K.A.R. 82-3-118) Will Be Guaranteed By Operator Or Agent.

Date: 4/17/2002

Authorized Operator/Agent:


JIM THATCHER

COPY: QUALITY WELL SERVICE
RUSSELL

RECEIVED

APR 19 2002
4-19-02
KCC WICHITA

15-007-01196-0000

SKINNER "D" NO. 5

Casing Records:

8 5/8" - 287'

5 1/2" - 4940'

Company: Aylward Drilling Company et al

Contractor: Aylward Drilling

Commenced: August 8, 1958

Completed: August 27, 1958

Location: NE SW SE

Sec. 3-32-15W

Barber County

Kansas

Elevation: 2019 R.B.

	From	To	Remarks
Sand	0	74	Set 8 5/8" surface pipe @ 287'
Red Rock & Gyp	74	287	w/250 sacks cement
Gyp & Red Rock	287	430	
Red Rock & Gyp	430	1150	Geological Tops:
Shale & Shells	1150	1850	Heebner Shale 4130
Lime & Shale	1850	2295	Base/Oread 4166
Lime	2295	2550	Douglas Sand 4208
Lime & Shale	2550	2660	Tonganoxie Sand 4300
Lime w/Shale	2660	2710	Lansing 4308
Lime & Shale	2710	2875	Base/K.C. 4752
Shale & Lime	2875	2960	Mississippian 4838
Lime w/Shale	2960	3060	R.T.D. 4940
Lime & Shale	3060	3120	
Shale & Lime Strks.	3120	3245	DST 4626-45 (Straddle test from 4807)
Shale w/Lime	3245	3350	Open 1 hr. Wk. bl. Rec. 45" Watery
Lime & Shale	3350	3430	mud. IBHP 1498#/20", FBHP 855#/30"
Shale & Limee	3430	3635	FP 35#-43#.
Lime & Shale	3635	3772	
Lime w/some Shale	3772	3835	DST 4876-4903 Open 40 min. Gas surf.
Lime & Shale	3835	4045	In 2 min., gauged 2,930 MCFG/5",
Mostly Lime - Some Shale	4045	4062	4,735 MCFG/15", leveled off at
Lime & Shale	4062	4234	4,925 MCFG/30". Rec. 60" Mdy & Gsy
Sandy Lime & Shale	4234	4268	oil. IBHP 1545#/20", FBHP 1528#/30"
Lime & Shale	4268	4332	FP 887#-1030#.
Mostly Lime - Some Shale	4332	4396	
Lime	4396	4845	DST 4894-4940 Open 45 min. Gas
Cherty Lime	4845	4883	surf./5", gauged 275 MCFG/8", 186
Lime	4883	4940 T.D.	MCFG/15". Flowed mud/35", flowed
			oil/40". IBHP 1540#/20", FBHP 1533#
			20". FP 420#-995#.
			Ran 5 1/2" Casing @ 4940' w/75 sacks
			cement.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Skinner

Subscribed and sworn to before me this 2nd day of September, 1958.

Diane Jessup
Notary Public

My commission expires December 11, 1961



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Petroleum Property Services, Inc.
155 N. Market, Ste 1010
Wichita, KS 67202-1824

April 24, 2002

Re: SKINNER D #5
API 15-007-01196-00-00
CNESWSE 3-32S-15W, 1100 FSL 1500 FEL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

A handwritten signature in dark ink, appearing to read "David P. Williams", is written over the word "Sincerely".

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888