

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1974
9-23-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Westmore Drig Co Inc

Complete Address Chapin Bldg Medicine Lodge, KS

Lease Name Skinner D Well No. 1

Location SE/SE/NE Sec. 3 Twp. 32 Rge. 15 (E) (W) W

County Barber Total Depth 4901

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 1:00 PM Day 20 Month 9 Year 1974

The above well was plugged as follows:

200 ft 8 5/8 surface cemented with 170 sacks. 4901 ft 5 1/2 long string
cemented with 50 sacks. Top perf. 4830 ft. Sand to 4200 ft, 5 sacks
cement with bailer. Pulled 3300 ft 5 1/2/ Set 10 ft rock bridge at
300 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 9/23/74
INV. NO. 9938-W