

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

SEP 02 1975  
9-2-75  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Atlantic Richfield Co

Complete Address 1112 11th St Woodward, OK

Lease Name T.L. Welsh C Well No. 1

Location SW/NE/NW Sec 17 Twp. 32 Rge. 15 (E) (W)W

County Barber Total Depth 4935

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Lillard Casing Pulling Co

Address Box 926 Woodward, OK License No. 618

Operation Completed: Hour 3:00 PM Day 29 Month 8 Year 1975

The above well was plugged as follows:

308 ft 10 3/4 surface cement circulated. 4933 ft 5 1/2 long string  
cemented with 200 sacks. Top perf. 4820 ft. Pump 35 sacks cement  
to 4700 ft. Pulled 4014 ft 5 1/2. Pump 2 sacks hulls, 10 sacks gel,  
50 sacks cement from 258' to 358'. Mud to 40 ft, plug, 10 sacks  
cement to surface. Weld plate on S.P.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 9/3/75

INV. NO. 1851-W