

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1963
10-28-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Schermerhorn Oil Corporation

Complete Address: P. O. Box 287, Tulsa 1, Oklahoma

Lease Name Davis Ranch "B" Well No. # 1

Location Center Sec. 19 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4935

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5:45PM Day 26th Month Oct. Year 1963

The Above well was plugged as follows:

852' of 8 5/8" surface pipe, cemented with 450 sacks. 4934' of 4 1/2" long
string, cemented with 60 sacks. Bottom of hole was sanded to 4880', and
cemented with 3 sacks. Hole was filled with mud to 240', 10' rock bridge,
cemented with 25 sacks. Hole was filled with mud to 40', 10' rock bridge,
cemented with 10 sacks to base cellar.

4520' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 10/28/63
INV. NO. 7954-W

Signed: Archie Elving
Well Plugging Supervisor