


 KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION
 APR 4 1966
 4-4-66
 CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name Time Petroleum Company

Complete Address: 815 Union National Bldg., Wichita, Kansas

Lease Name Davis Ranch Well No. # 1

Location C SW NE Sec. 19 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4877'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:15 PM Day 1st Month April Year 1966

The Above well was plugged as follows:

265' of 8 5/8" surface pipe, cement circulated. 4876' of 4 1/2" long string,
cemented with 75 sacks. Plug abck T.D. 4840'. Top perferation 4809'. Bottom
of the hole was sanded to 4790', and cemented with 3 sacks. 4444' of 4 1/2"
long string was recovered from the hole. Fluid in the hole was bailed down
to 260', bridge plug and rock bridge from 260' to 250', and cemented with
25 sacks. Hole was filled with mud to 40', rock bridge from 40' to 30',
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/4/66

INV. NO. 2984-W

Signed: Archie Elving
 Well Plugging Supervisor