



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1975
S-19-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Shenandoah Oil Corp

Complete Address 230 Hightower Bldg Oklahoma City, OK

Lease Name Robert Anderson Well No. 1

Location 350' NB/ C E/2 Sec. 11 Twp. 34 Rge. 14 (E) (W)

County Barber Total Depth 4858

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lillard Casing Pulling Co

Address Box 962 Woodward, OK License No. 618

Operation Completed: Hour 3:00 PM Day 15 Month 5 Year 1975

The above well was plugged as follows:

364 ft 8 5/8 surface cement circulated. 4856 ft 4 1/2 long string
cemented with 125 sacks. Top perf. 4747 ft. Pump sand, 15 sacks
cement to 4700 ft. Pulled 3628 ft 4 1/2. Pump 2 sacks hulls, 10 sacks
gel, 50 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5/21/75
INV. NO. 1354-W