

*14*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 23 1963

12-23-63

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Socony Mobil Oil Co., Inc.

Complete Address: 300 N. Broadway, Wichita, Kansas

Lease Name Roxie Kincaid Estate Well No. # 1

Location SE SW Sec. 11 Twp. 34 Rge. 14 (E) (W) W

County Barber Total Depth 4870

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:00AM Day 21st Month December Year 1963

The Above well was plugged as follows:

353' of 8 5/8" surface pipe, cement circulated. 4785' of 4 1/2" long string,  
cemented with 100 sacks. Top perferation 4726'. Bottom of hole sanded to  
4700', cemented with 4 sacks. Hole was filled with mud to 300', 10' rock  
bridge, cemented with 25 sacks. Hole was filled with mud to 40', 10' rock  
bridge, cemented with 10 sacks to base cellar.  
3620' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-24-63

INV. NO. 8327W

Signed: Archie Elving  
Well Plugging Supervisor