

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed November 27, 1967.

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas 67202

Lease Name Robbins Unit Well No. # B-1

Location App. W/2 NE Sec. 24 Twp. 31 Rge. 16 (E) (W)W

County Comanche Total Depth 4911'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas 67530 License No. _____

Operation Completed: Hour 1:30AM Day 13th Month December Year 1967

The Above well was plugged as follows:

511' of 8 5/8" surface pipe, cement circulated with 350 sacks. Hole was
filled with drilling mud to 500', 1st cementing plug, bridged with 1/2 sack
of hulls on fluid at 500', and cemented with 25 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls
on fluid at 40', and cemented with 10 sacks, with cement from 30' to the
base of the cellar. Rat and mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED

DATE 12/18/67
INV. NO. 6928-W