

LEASE NAME Bair

WELL NUMBER C-1

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 34 TWP. 35 RGE. 14 (BY) (W) AKC

COUNTY Barber

Date Well Completed 6-4-76

Plugging Commenced 4-16-96

Plugging Completed 4-22-96

LEASE OPERATOR Oxy U.S.A.

ADDRESS 400 S. Main, Pratt, KS 67124

PHONE# (316) 672-5630 OPERATORS LICENSE NO. 5447

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-16-96 (date)

by Steve Middelton (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Miss Cherokee Depth to Top 4832 Bottom 4876 T.D. 4885

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	428	None
				4 1/2	4927	Approx 3100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Lay down rods and tubing, sand well back to 4748, dump 45 portland cement with dump bailer, stretch and cut pipe at 3100, lay down 4 1/2 casing, Allied pump 300 CSH, 10 jel, 50 cement, 10 jel, 100 #CSH, 8 5/8 wiper plug, 100 cement 60/40 6% jel, max PSI 350

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy U.S.A.

STATE OF Kansas COUNTY OF Barber, ss.


Alan Vratil

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 23 day of April, 1996

My Commission Expires: 10/14/98

[Signature]
Notary Public

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 23 1996
2-23-96

CONSERVATION DIVISION
WICHITA, KS

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Baier "C" #10W
Sec 34-34S-14W
Barber County Kansas

Commenced: 3-24-76

Completed: 8-4-76

OPERATOR: CITIES SERVICE OIL CO.

From	Depth to	Formation	Remarks
0	400	Sand-Clay	Ran 10 jts of 24# 8 5/8" csg set @ 428' Cemented w/ 300 sks 50/50 Posmix 27 CC PD @ 7:50 a.m. 3-25-76
400	1157	Redbed	
1157	1625	Shale	
1625	1665	Anhy	
1665	1880	Shale	
1880	2197	Shale-Shells	
2197	2733	Shale-Lime	
2733	3290	Lime-Shale	
3290	3327	Shale-Lime	
3327	4600	Lime-Shale	
4600	4680	Lime	Ran 152 jts of 1 1/2" # 355 4 1/2" csg set @ 4927' Cemented w/250 sks Class A .75% CFR-2 + 10% Salt PD @ 4:45 p.m. 4-4-76
4680	4795	Lime-Shale	
4795	4928	Lime	
	4928 - TD		

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled Sec 34-34S-14W, Barber County, Kansas to the best of my knowledge and belief.

James S. Sutton II
JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 12th day of April, 1976, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS - Notary PUBLIC

My Commission Expires: February 6, 1979.

