


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Comanche County, Sec. 23 Twp. 31 Rge. 16 (E) W (W)

Location as "NE/CNW&SW&" or footage from lines SE NE NW  
Lease Owner Barbara Oil Company  
Lease Name Robbins Rahcn Well No. 1  
Office Address Central Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed February 1953 19  
Application for plugging filed August 12, 1959 19  
Application for plugging approved August 17, 1959 19  
Plugging commenced 9-10-59 19  
Plugging completed 9-14-59 19  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production August 1958 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Lackamp, Stafford, Kansas  
Producing formation Mississippi Depth to top 4886 Bottom Total Depth of Well 4926 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
				12 1/2"	301'	None
				7"	4891'	3029'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill hole from 4900' to 4870' with chat; dump 6 sacks cement with bailer. shoot pipe loose at 3020' and pull pipe. Mud up to 250', put in 10' rock bridge and 30 sacks cement. Mud up to 40', put in 10' rock bridge and 15 sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 29 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Arnett Casing Pulling Co.  
Address Hoisington, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L.W. Davidson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L.W. Davidson  
L.W. Davidson  
322 Central Building, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 59

My commission expires March 2, 1961  
Mildred Fisher Notary Public.



Barbara Oil Company  
 Robbins Well # 1  
 Total Depth  
 Comm.  
 Rotary Comp  
 Cable Tools Comp

4926  
 12/15/53  
 1/14/53  
 2/10/53

Location Cor. SE 1/4, NE 1/4, NW 1/4.  
 Section 25-T31S-R16W Comanche Co., Ks.  
 CASING RECORD.  
 12 1/2" Casing at 301 Ft  
 Cemented with 400 Sacks Cement  
 7" Casing at 4891 Ft.  
 Cemented with 350 Sacks Cement

Clay	20
Sand	106
Red Shale	190
Shale & Shells	300
Shale & Lime	311
Red Shale & Shells	1235
Shale & Shells	1625
Shale & Salt	1635
Shale & Shells	1940
Anhydrite & Shale	2150
Shale & Lime	2550
Lime	2557
Shale & Lime	3120
Shale	3245
Shale & Lime	3575
Lime	3600
Shale & Lime	3680
Lime	3730
Shale & Lime	3792
Lime	3974
Shale & Lime	4056
Lime	4241
Shale & Lime	4395
Lime	4416
Lime Soft	4428
Lime	4791
Shale & Lime	4836
Lime	4880
Shale & Lime	4886
Lime Cherty	4918
Shale Green	4919
Chert	4922
Chert Hard	4926
Total Depth	4926

Tops.

Douglas Sand Zone	4270-84
Lansing K. C.	4284
Mississippian	4886
All depths from Top Bushing	
4 1/2 Feet above Ground.	

**RECEIVED**  
 STATE CORPORATION COMMISSION

AUG 13 1959

CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

R. C. PATTON CO.,

By R.C. Patton

Subscribed and sworn to before me this 18th day of February 1953

J.P. Henderson  
 Notary Public..

My Commission Expires Oct 4th 1958

PLUGGING  
 FILE SEC. 23 T 31 R 16w  
 BOOK PAGE 60 LINE 4