


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barber County, Sec. 4 Twp. 32 Rge. (E) 15 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNWxSWx" or footage from lines NW NW NE
Lease Owner Aylward Drilling Company
Lease Name Skinner "D" Well No. 8
Office Address 813 1st National Bank Bldg. - Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 18 19 60
Application for plugging filed September 18 19 60
Application for plugging approved September 18 19 60
Plugging commenced September 18 19 60
Plugging completed September 18 19 60
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hample
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	262'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 250 ft.
Set plug at 250 ft. with 20 sacks cement
Filled with mud to 35 ft.
Set plug at 35 ft. with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1960
11-21-60
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Aylward Drilling Company
Address 813 1st National Bank Bldg. - Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Charles D. Williams (employee of owner) ~~is~~ ~~known~~ ~~proprietor~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles D. Williams
813 1st Nat'l Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of September, 1960

My commission expires December 11, 1961
Duane Jessup
DUANE JESSUP Notary Public.



8

SKINNER "D" NO. 8

Casing Record: Company: Aylward Drilling Company et al Location: NW NW NE 4-32-15W
 8 5/8" - 262' Contractor: Aylward Drilling Company Barber County
 Kansas
 Commenced: September 4, 1960
 Completed: September 18, 1960 Elevation: 1928 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Red Rock	0	105	Set 8 5/8" surface pipe @ 262'
Gyp	105	120	w/200 sacks cement.
Red Bed	120	245	
Red Bed & Sand	245	765	Geological Tops:
Red Bed & Shale	765	925	
Shale	925	1060	Heebner 4015
Shale & Red Rock	1060	1240	Douglas Sand 4091
Shale & Shells	1240	1560	Brown Lime 4198
Shale	1560	1750	Lansing 4223
Shale & Lime	1750	2130	B/Kansas City 4603
Lime	2130	2295	Marmaton 4620
Lime & Shale	2295	2400	Mississippian 4743
Lime w/some Shale	2400	2480	
Lime & Shale	2480	2705	DST 4745-4800 Open 1 hr. Fair blow
Lime w/some Shale	2705	2810	for 15", strong remainder of test.
Shale	2810	2830	Rec. 240' mud. IBHP 420# -
Lime & Shale	2830	3160	FBHP 345#. FP 150#-160#.
Shale & Shells	3160	3310	
Lime & Shale	3310	3580	DST 4625-4865 Open 1 hr. Str. blow.
Shale & Lime	3580	4035	Rec. 120' mud. IBHP 600# -
Lime & Shale	4035	4175	FBHP 580#. FP 180#-200#.
Shale & Lime	4175	4230	
Lime	4230	4690	
Lime & Shale	4690	4800	
Shale & Lime	4800	4865 T.D.	D & A

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Charles D. Williams

Subscribed and sworn to before me this 20th day of September, 1960

Duane Jessup
 DUANE JESSUP Notary Public

My commission expires December 11, 1961

RECEIVED
 STATE CORPORATION COMMISSION

NOV 21 1960
 11-21-60
 CONSERVATION DIVISION
 Wichita, Kansas