

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-01192-0000

LEASE NAME Skinner

WELL NUMBER C-3

         Ft. from S Section Line

         Ft. from E Section Line  
NW NE SW

SEC. 2 TWP. 32 RGE. 15 (E) or (W)

COUNTY Barber

Date Well Completed         

Plugging Commenced 4-13-88

Plugging Completed 4-26-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR N.C.R.A.

ADDRESS P.O. Box 6  
Great Bend, Kansas 67530

PHONE# (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify?          Dist. # 1 Dodge City, Kansas

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4935'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	200'	none
				5-1/2"	4932'	3927'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped bottom with 1 sack hulls and 20 sacks common to 4800', shot pipe @4400', 3927', pulled a total of 124 joints of 5-1/2" casing. Plugged surface with 3 sacks hulls 10 sacks gel, released plug and 125 sacks 65/35 pos and 8% gel.  
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) Box 347 Chase, Kansas 67524


SUBSCRIBED AND SWORN TO before me this 29th day of April, 19 88

RECEIVED  
STATE CORPORATION COMMISSION

*Jane Lowe*  
Notary Public

My Commission Expires:

MAY 02 1988  
5-2-88



CONSERVATION DIVISION  
Wichita, Kansas

15-007-01192-0000

N.C.R.A. SKINNER "C" NO. 3

Casing Records:

Company: National Cooperative Refinery Ass'n  
Contractor: Aylward Drilling Company

Location: NW NE SW 2-32-15W  
Barber County  
Kansas

8 5/8" - 200'  
5 1/2" - 4932'

Commenced: May 21, 1958  
Completed: June 14, 1958

Elevations 1965 KB

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	60	Set 8 5/8" surface pipe @ 200' w/175 sacks cement.
Sand & Red Rock	60	85	
Red Rock & Sand	85	110	
Gyp Rock - Hard	110	128	<b>Geological Topics</b>
Red Rock & Grey Shale	128	202	
Red Rock	202	800	Hoebner 4076
Red Rock & Gyp	800	1300	Toronto 4092
Red Rock & Shale	1300	1450	Douglas 4112
Shale & Shells	1450	2120	Douglas Sand 4142
Line & Shale	2120	2200	Lansing 4255
Mostly Lime	2200	2260	W/Kansas City 4699
Lime	2260	2820	Messey 4721
Lime & Shale	2820	3150	Basal Penn.
Shale & Lime	3150	3400	Cong. Sand 4790
Lime & Shale	3400	4150	Alas. 4815
Sandy Shale	4150	4255	Kinderhook 4904
Lime	4255	4704	A.T.O. 4989
Shale & Lime	4704	4738	
Lime	4738	4766	
Lime w/shale streaks	4766	4788	DST 4714-38 (Corrected to 4708-32)
Lime w/some shale	4788	4817	Open 1 hr. Vry wh. bl. dying in several minutes. Rec. 12" mud. 18MP 1154/20".
Lime	4817	4865	18MP 454/20". PP 85-454.
Lime - Cherty	4865	4915	
Lime	4915	4935 T.O.	

DST 4714-38 (Corrected to 4708-32)  
Open 1 hr. Vry wh. bl. dying in several minutes. Rec. 12" mud. 18MP 1154/20".  
18MP 454/20". PP 85-454.

UST 4796-4810 (corrected to 4790-4834)  
Open 1 hr. Gas to surf. in 5". Gauged 439,000 in 15" & 165,000 remainder of hr.  
18MP 17383/20", 18MP 16585/20". PP 180-1304.

DST 4810-65 (Corrected to 4834-59)  
Open 1 hr. Gas to surf. in 7". Gauged 76,000 in 10". 44,000/15", not str. enough to gauge after 15". Flowed oil in 55".  
18MP 16525/20", 18MP 15284/20".  
PP 3154-9124.

UST 4865-95 (Corrected to 4839-89)  
Good str. bl. w/gas to surf. in 4".  
Gauged 362,000/5", 28,000/10". Oil in 13".  
18MP 15343/20", 18MP 15254/20".  
PP 8704-11724.

Set 5 1/2" casing @ 4932' w/50 sacks cement.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul Whisenand

Subscribed and sworn to before me this 16th day of July, 1958.

Duane Jessup  
DUANE JESSUP  
Notary Public

My commission expires December 11, 1961.

RECEIVED  
CORPORATION COMMISSION  
MAR 24 1988  
3-24-88  
CONSERVATION DIVISION  
Wichita, Kansas

