


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 19 Twp. 34 Rge. (E) 14 (W)  
Location as "NE/CNW&SW&" or footage from lines C/NW SE  
Lease Owner Time Petroleum Company  
Lease Name Davis Ranch Well No. 3  
Office Address 815 Union National Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 11 19 64  
Application for plugging filed May 11 19 64  
Application for plugging approved May 11 19 64  
Plugging commenced May 11 19 64  
Plugging completed May 11 19 64  
Reason for abandonment of well or producing formation Dry Hole



If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4905 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	263'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Plugged hole as follows: Plugged at 250' with 25 sacks of cement and 1/4 sack of hulls and mud to 40'; plugged with 10 sacks of cement and 1/4 sack of hulls. Plugged rat hole with 2 sacks of cement and also put 2 sacks of cement in the mouse hole. Job completed at 11:15 A. M. May 11, 1964.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 14 1964  
5-14-64  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Jim B. McWilliams (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams, Secy-Treas.  
P. O. Box 355, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 64

My commission expires December 14, 1965

Elaine H. Taylor, Notary Public.

15-007-01476-0000

D R I L L E R S    L O G

#3 Davis Ranch

CASING RECORD: Ran 263' of 8-5/8" surface casing.	COMPANY: Time Petroleum Company	DESCRIPTION: C/NW SE Section 19-34S-14W Barber County, Kansas
TOTAL DEPTH: 4905'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 1674' RB 1669' GL
	COMMENCED: April 29, 1964	
	COMPLETED: May 11, 1964	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed & Shale	0	665	Ran 263' of 8-5/8" surface casing; set and cemented at 263' with 200 sacks of regular cement, 2% gel and 3% calcium chloride. Plug down at 7:00 A. M. April 30, 1964. Cement circ..
Red Bed & Shale	665	1006	
Shale	1006	1890	
Shale & Lime	1890	2300	
Lime	2300	2425	
Lime & Shale	2425	4115	DST #1 4815'-4850' tool open 1 hour, weak blow 5 minutes. Flushed tool. Recovered 20' mud, no show of oil. IBHP 137 lbs. in 1 hour. IFP 42 lbs. FFP 42 lbs. FBHP 84 lbs. in 1 hour.
Shale	4115	4193	
Lime	4193	4561	
Lime & Shale	4561	4814	
Lime	4814	4905	

TOTAL DEPTH 4905'

DST #2 4850'-4870' tool open 1 hour, weak blow 25 minutes. Flushed tool. Recovered 20' mud, no show of oil. IBHP 121 lbs. in 1 hour. IFP 40 lbs. FFP 63 lbs. FBHP 94 lbs. in 1 hour.

D. & A.

Plugged hole as follows: Plugged at 250' with 25 sacks of cement and 1/4 sack of hulls and mud to 40'; plugged with 10 sacks of cement and 1/4 sack of hulls. Plugged rat hole with 2-sacks of cement and also put 2 sacks of cement in the mouse hole. Job completed at 11:15 A. M. May 11, 1964.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

**RECEIVED**  
STATE CORPORATION COMMISSION  
5-14-64  
MAY 14 1964

*Jim B. McWilliams*  
Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 12th day of May, 1964.

**CONSERVATION DIVISION**  
Wichita, Kansas

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1965