

15-007-01516-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barber County, Sec. 19 Twp. 34 Rge. (E) 14 (W)

Location as "NE/CNW%SW%" or footage from lines C/NE SW
Lease Owner Time Petroleum Company
Lease Name Davis Ranch Well No. 2
Office Address 815 Union National Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 27 19 64
Application for plugging filed April 27 19 64
Application for plugging approved April 27 19 64
Plugging commenced April 27 19 64
Plugging completed April 27 19 64
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4920 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	278'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole as follows: Plugged at 260' with 1/4 sack of hulls and 25 sacks of cement and mud to 40'; plugged with 1/4 sack of hulls and 10 sacks of cement. Plugged rat hole with 2 sacks of cement and also put 2 sacks of cement in the mouse hole. Job completed at 1:00 P. M. April 27, 1964.

RECEIVED
STATE CORPORATION COMMISSION
MAY 1 1964
S-1-64
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of April, 19 64

My commission expires December 14, 1965
Elaine H. Taylor, Notary Public.

D R I L L E R S L O G

#2 DAVIS RANCH

CASING RECORD:
Ran 270.55' of new
8-5/8" surface
casing.
TOTAL DEPTH:
4920'

COMPANY: Time Petroleum Company
CONTRACTOR: Strata Drilling, Inc.
COMMENCED: April 15, 1964
COMPLETED: April 27, 1964

DESCRIPTION: C/NE SW
Section 19-34S-14W
Barber County, Kansas
ELEVATION: 1697' KB

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed	0	497	Ran 270.55' of new 8-5/8" surface casing;
Shale & Red Bed	497	1005	set and cemented at 278' with 200 sacks
Shale	1005	1660	of regular cement, 2% gel and 3% calcium
Shale & Shells	1660	2025	chloride. Plug down at 9:30 A. M. April
Lime	2025	2350	16, 1964. Cement circulated.
Lime & Shale	2350	2650	
Shale & Shells	2650	2870	
Lime & Shale	2870	3275	DST #1 4837'-4870' tool open 1 hour, weak
Lime	3275	3450	blow for 5 minutes. Flushed tool. Recover-
Lime & Shale	3450	3825	ed 20' mud, no show of oil or gas. ISIP
Shale	3825	4005	73 lbs. IFP 42 lbs. FFP 52 lbs. FSIP
Shale & Lime	4005	4228	52 lbs. in 1 hour.
Lime	4228	4255	
Lime & Shale	4255	4360	DST #2 4866'-4900' packer failed.
Lime	4360	4740	
Lime & Shale	4740	4809	DST #2 Rerun 4830'-4900' weak blow 2 hours.
Lime	4809	4834	Recovered 20' mud, no show of oil or gas.
Lime & Chert	4834	4870	ISIP 179 lbs. IFP 10 lbs. FFP 16 lbs.
Lime	4870	4920	FSIP 63 lbs. in 1 hour.

TOTAL DEPTH 4920'

DST #3 4900'-4920' tool open 2 hours; weak
to fair blow. Recovered 30' mud. ISIP 147
lbs. IFP 42 lbs. FFP 50 lbs. FSIP 115 lbs.
in 1 hour.

D. & A.

Plugged hole as follows: Plugged at 260'
with $\frac{1}{4}$ sack of hulls and 25 sacks of cement
and mud to 40'; plugged with $\frac{1}{4}$ sack of hulls
and 10 sacks of cement. Plugged rat hole
with 2 sacks of cement and also put 2 sacks
of cement in the mouse hole. Job completed
at 1:00 P. M. April 27, 1964.

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1964
5-1-64
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of
my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 29th day of April, 1964.

My Commission Expires:
December 14, 1965

Elaine H. Taylor
Elaine H. Taylor, Notary Public