


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barber County, Sec. 34 Twp. 34S Rge. 14 (E) W. (W)
Location as "NE/CNW&SW" or footage from lines C NE NW
Lease Owner Crescent Oil and Gas Corporation
Lease Name Neu Well No. 1
Office Address P.O. Box 412, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6/8/63 As a dry hole 19 63
Application for plugging filed June 8 19 63
Application for plugging approved June 8, Verbally 19 63
Plugging commenced June 8 19 63
Plugging completed June 8 19 63
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Dry-None Depth to top Bottom Total Depth of Well 4900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	354	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped in heavy mud from total depth to 240'. Set plug in 10 3/4" surface at 240'. Ran 25 sacks of cement on top of plug through drill pipe. Put mud and hulls on top of cement to 35'. Ran second plug and cemented to the surface.
Plugged and Abandoned

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1963
6-17-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drlg. Co.
Address 1720 Wichita Plaza, Wichita 2, Kansas

STATE OF , COUNTY OF , ss.
 (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl E. Stacey
P.O. Box 485, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1963

Yvonne M. Stevenson, Notary Public
My commission expires

Notary Public.

DRILLERS LOG

Neu #1

CASING RECORD:	COMPANY:	Crescent Oil and Gas Corp.	DESCRIPTION:
10 3/4" @ 342'	CONTRACTOR:	Red Tiger Drilling Co.	Center NE NW
w/ 250 sx cement	COMMENCED:	May 24, 1963	S4-34S-14W
TOTAL DEPTH: 4900	COMPLETED:	June 7, 1963	Barber County, Kansas
			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	105	
Sand & Clay	105	200	
Shale & Gyp & Sand	200	372	
Shale & Shells	372	1403	
Shale & Lime & Shells	1403	1864	
Anhydrite	1864	1703	
Shale & Shells	1703	1825	
Lime & Shale	1825	3806	
Sand	3806	3915	
Sand & Shale	3915	4005	
Shale & Lime	4005	4195	
Lime	4195	4790	
Lime & Chert	4790	4863	
Lime	4863	4900	

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1963

6-21-63
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 11th day of June, 1963.

Doraine V. Head
Notary Public

My Commission Expires:

11-17-66