

15-007-30296-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 11 Twp. 34S Rge. (E) 14 (W)
Location as "NE/CNWxSWx" or footage from lines 350' NE of C-E/2
Lease Owner Shenandoah Oil Corporation
Lease Name Robert Anderson Well No. #1
Office Address 230 Hightower Bldg., Oklahoma City, Oklahoma 73102
Character of Well (completed as Oil, Gas or Dry Hole) GAS
Date well completed May 19.67
Application for plugging filed March 25 19.75
Application for plugging approved March 31 19.75
Plugging commenced May 11 19.75
Plugging completed May 15 19.75
Reason for abandonment of well or producing formation Formation depleted.

If a producing well is abandoned, date of last production April 1, 19.75
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation Mississippi Depth to top 4747 Bottom 4777 Total Depth of Well 4858 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Casing	0	381	8 5/8	381	0
	Casing	0	4803	4 1/2	4858	3620

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped heavy mud from T.D. to 415'
50 sx common cement plug from 415' to 315'
Heavy mud from 315 to 35'
15 sx common cement plug from 35' to 5'

Cut off 8 5/8" surface casing 3' below ground level
Weld on Steel Plate. Job complete 3:00 p.m. 5-15-75

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1975
5-21-75
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lillard Casing Pullers
Address P.O. Box 962 Woodward, Oklahoma 73801

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
Donald F. Nowak (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald F. Nowak, Asst. Dir. Prod. Supp.
230 Hightower Bldg. - Oklahoma City, Okla 73102
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May 1975

My commission expires January 3, 1979

Mary M. Pulliam
Notary Public.

DRILLER'S LOG

COMPANY:	Shenandoah Oil Corporation
CONTRACTOR:	LEBEN DRILLING, INC.
FARM:	ROBERT G. ANDERSON #1
LOCATION:	C SE NE SEC. 11-34S-14W BARBER COUNTY, KANSAS
COMMENCED:	11-30-66
COMPLETED:	12-14-66

0	364	Shale, Sand
364	1120	Shale
1120	1565	Red Shale
1565	1580	Anhydrite
1580	1630	Shale
1630	2230	Shale, Lime
2230	2625	Lime
2625	3490	Lime, Shale
3490	3599	Lime
3599	3910	Shale, Lime
3910	4858	Lime
	<u>4858</u>	<u>RTD - Set 4 1/2" Casing</u>

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1975
4-1-75
CONSERVATION DIVISION
Wichita, Kansas


8 5/8" new 20# surface casing set 381' cemented with 250 sacks
Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Robert G. Anderson #1 Well, located C SE NE of Section 11, Township 34 South, Range 14 West, Barber County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 20th day of December, 1966.



Ulanda Nichols
Ulanda Nichols

My Commission Expires:
April 1, 1967