


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County. Sec. 11 Twp. 34S Rge. 11 (E) (W) X  
Location as "NE/CNW&SW" or footage from lines. NE SE SW  
Lease Owner. Mobil Oil Company  
Lease Name. Roxie Kincaid Estate Well No. 1  
Office Address. P. O. Box 335 Attica, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 12-17-63 19  
Plugging completed 12-21-63 19  
Reason for abandonment of well or producing formation Dry  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation Depth to top Bottom Total Depth of Well 1870 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	353	None
				4 1/2	None	3630

RECEIVED  
STATE CORPORATION COMMISSION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method of methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

DEC 20 1963

12-26-63  
CONSERVATION DIVISION  
Wichita, Kansas

Moved in. Cleaned out cellar. Sanded to 1700'. Dumped 4 sacks of cement.  
Rigged up. Working pipe. Shot at 1300'.  
Loaded hole with water. Working pipe. Shot at 1200' - 1100' - 1000' - 3900' - 3800' - 3700' - 3620'. Pulling pipe.  
Pulling pipe. Bailing. Pushed plug to 300'. Build rock bridge. Dumped 5 sacks of cement.  
Bailed hole to 285'. Dumped 20 sacks of cement. Filled hole with mud to 140'. Build rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of December 1963

Glad O. [Signature]

Notary Public.

My commission expires May 27, 1964

15-007-11682-0000  
**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas


**COPY**

Company- **SOCONY MOBIL OIL CO.**  
 Farm- **Roxie Kincaid Est. No. 1**

SEC. **11** T. **34** R. **14W**  
**50' W of NE SE SW**

Total Depth. **4870'**  
 Comm. **7-15-60** Comp. **11-3-60**  
 Shot or Treated.  
 Contractor. **Peel Brothers, Inc.**  
 Issued. **1-28-61**

County **Barber**  
**KANSAS**



**CASING:**  
 8 5/8" **353'** cem w/425 sx.  
 4 1/2" **4785'** cem w/175 sx.

Elevation. **1618'** GL

Production. **1,090,000** MCFPD

	Figures Indicate Bottom of Formations.
redbed	30
water & redbed	255
redbed, shale & shells	845
shale & shells	1370
shale & lime	1890
broken lime	1960
lime	2110
lime & shale	4103
lime	4870
Total Depth	

<b>TOPS:</b>	
Heebner	3921
Toronto	3936
Douglas	3959
Lansing-Kansas City	4101
Marmaton	4616
St. Louis	4717

Acidized OH 4785' to 4870' w/1000 gal.  
 BDA acid.  
 Sand frac OH 4785' to 4870' w/45,000# 10/20 sand  
 In 45,000 gal 5% HCl acid.  
 Perf. 4726-65' w/78 holes. Acidized w/1000 gal  
 BDA.  
 Sand frac perf 4726-65' w/20,000# 20/40 sand +  
 5,000# 10/20 sand + 25,000 gal. 6.2% acid.  
 Treat perf 4726-65' and OH 4765'-4870' w/2000  
 gal. 6% HCl w/6000# CaCl.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JUL 16 1964  
 7-16-64  
 CONSERVATION DIVISION  
 Wichita, Kansas