

File
Sims A#1


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 11 Twp. 34 Rge. 14 (E) (W)
Location as "NE/CNW&SW" or footage from lines. C NE NW
Lease Owner Robert F. White
Lease Name Sims A#1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19.
Application for plugging filed 19.
Application for plugging approved 19.
Plugging commenced 4/10/71 19.
Plugging completed 4/14/71 19.
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4840' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	394	none
				4 1/2"	4840'	3435'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran sand to 4725', ran 4 sacks of cement. Shot pipe at 3510', loaded hole with water, shot pipe at 3450' and worked pipe loose, pulled 106 joints. Bailed hole to 325', set 20' rock bridge and ran 6 yards concrete. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1971
4-23-71
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and sworn to before me on this 16th day of April, 1971.
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires Feb. 15, 1975

Margaret Melcher
Notary Public.

DRILLER'S LOG

COMPANY: Shenandoah Oil Corporation
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: MILDRED SIMS A-1
 LOCATION: C NE NW SECTION 11-34S-14W
 BARBER COUNTY, KANSAS
 COMMENCED: 5-17-67
 COMPLETED: 5-27-67

0	1684	Redbed
1684	1830	Shale, Shells
1830	2070	Lime, Shale
2070	2716	Lime
2716	4251	Lime, Shale
4251	4840	Lime
	<u>4840</u>	<u>RTD - Set 4 1/2" Casing</u>

8 5/8" new 20# surface casing set to 394.15' cemented with 250 sacks Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Mildred Sims A-1 Well, located C NE NW of Section 11, Township 34 South, Range 14 West, Barber County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 29th day of May, 1967.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1971

RECEIVED
 STATE CORPORATION COMMISSION
 APR 6 1971
 CONSERVATION DIVISION
 Wichita, Kansas