

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 6 1963
 5-6-63

CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Dean McLemore of Jones & Gebert Oil Co. has this
 date requested permission to plug the following described well:

Mr. McLemore guarantees payment of the plugging fee.

Operator's full Name: Jones & Gebert Oil Co.

Complete Address: 205
1007 Central Bldg., Wichita, Kansas

Lease Name: McGrath Well No. # 1

Location: C SE NW Sec. 16 Twp. 33 Rge. 14 (E) (W) W

County Barber Total Depth 4751 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. McLemore was instructed to plug the well as follows:

812' of 8 5/8" surface pipe, cement circulated with 400
sacks. Fill hole to 805', 1st cementing plug, 1/4 sack hulls,
cement with 25 sacks. Fill hole with mud to 450', 2nd
cementing plug, 1/4 sack hulls, cement with 25 sacks. Fill
hole with mud to 40', 3rd cementing plug, 1/4 sack hulls,
cement with 15 sacks to base cellar. Rat hole 2 sacks.
 Very truly yours,

Archie Elving
 Conservation Division Agent