

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 16 1965
2-16-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ray Rice of Group Exploration has this
date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: James E. Ely

Complete Address: Box 127, Sterling, Kansas

Lease Name: Ely Well No. # 1

Location: C NW NE Sec. 20 Twp. 33 Rge. 14 (E)(W) W

County Barber Total Depth 4874' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

945' of 8 5/8" surface pipe, cement circulated with 650 sacks.
Fill hole with drilling mud to 275', 1st cementing plug, bridge
with hulls and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat holt with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent