

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 2 1962
 11-2-62
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Caseing Pulling Co. has this Oct 26 date requested permission to plug the following described well:

Mr. D. B. Pully guarantees payment of the plugging fee.

Operator's full Name: Socony Mobil Oil Co. Inc.

Complete Address: 300 N. Broadway Wichita, Kansas.

Lease Name: Wm. A. Wheat Unit "A" Well No. #1

Location: C W/2 SE Sec. 34 Twp. 33 Rge. 14 (E) (W) X

County Barber Total Depth 4713' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. D. B. Pully was instructed to plug the well as follows:

4688' of 4½" oil string set with 150 sacks cement. Hole sanded to 4680' and 3 sacks cement with baler. 1249' of 8 5/8" surface pipe circulated with cement. Hole filled with mud to 300', 10' rock bridge and 20 sacks cement. Hole filled with mud to 40', 10' rock bridge and 10 sacks cement to base of cellar.

Very truly yours,

Herman Gustus
 Conservation Division Agent