

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS, 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 27 1965  
4-27-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ted Dix of Skelly Oil Company has this

date requested permission to plug the following described well:

Mr. Dix guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name: Fred G. Roth Well No. # 1

Location: NE SE SW Sec. 36 Twp. 33 Rge. 14 (E) (W) W

County Barber Total Depth 5227' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dix was instructed to plug the well as follows:

357' of 8 5/8" surface pipe, cement circulated with 200 sacks.  
Fill hole with drilling mud to 300', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent