



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
AUG 30 1965
8-30-65
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Royal Wenrick of Lario Oil & Gas Company has this date requested permission to plug the following described well:

Mr. Wenrick guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Company

Complete Address: 301 S. Market, Wichita, Kansas

Lease Name: Margaret M. Lenkner Well No. # 1

Location: C SW Sec. 35 Twp. 33 Rge. 14 (E) (W) W

County Barber Total Depth 4860' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wenrick was instructed to plug the well as follows:

401' of 8 5/8" surface pipe, cement circulated with 400 sacks.
Fill hole with drilling mud to 300', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving