



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1975
3-13-75
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Copeland of D.R. Lauck Drlg has this

date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: D.R. Lauck Oil Co Inc

Complete Address: 301 S Broadway Wichita, KS

Lease Name: Wilson A Well No. 1

Location: SE/SE/SE Sec. 27 Twp. 24s Rge. 13 (E)(W) W

County: Stafford Total Depth 4218 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

320 ft 8 5/8 surface cemented with 275 sacks. Pump plug,
40 sacks cement to 500 ft. 2nd plug at 300 ft, 35 sacks
cement. Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks cement
to surface. 2 sacks cement in rat hole.

Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,

Russell B. Roberts
Conservation Division Agent