

14

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1962
11-2-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Socony Mobil Oil Co. Inc.

Complete Address: 300 N. Broadway Wichita, Kansas.

Lease Name Wm. A. Wheat Unit "A" Well No. #1

Location C W/2 SE Sec. 34 Twp. 33 Rge. 14 (E) (W) X

County Barber Total Depth 4713'

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Caseing Pulling Co.

Address: Box 221 Great Bend, Kansas. License No. 49

Operation Completed: Hour 5/30 ^{pm} Day 30 Month Oct Year 1962

The Above well was plugged as follows:

~~4688' of 4 1/2" oil string set with 150 sacks cement. Hole sanded to 4680' and 3 sacks cement with baler. 1249' of 8 5/8" surface pipe circulated with cement. Hole filled with mud to 300'. 10' rock bridge and 20 sacks cement. Hole filled with mud to 40'. 10' rock bridge and 10 sacks cement to base of cellar.~~

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Herman J.ustus*
Well Plugging Supervisor

DATE 11/2/62

INV. NO. 5953-W