

15-007-116650-0000

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-22-68
JAN 22 1968
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued December 22, 1967.
Corrected Authority,
issued January 8, 1968.Operator's Full Name Champlin Petroleum CompanyComplete Address: P. O. Box 308, Ellinwood, Kansas 67526Lease Name Davis Ranch "F" Well No. # 1Location C SE NW Sec. 31 Twp. 33 Rge. 14 (E) (W)WCounty Barber Total Depth 4982'Abandoned Oil Well Gas Well X Input Well SWD Well D & AOther well as hereafter indicated: Plugging Contractor: Pipe Pullers, Inc.Address: Box 486, Ellinwood, Kansas 67526 License No. 462Operation Completed: Hour 1:15PM Day 20th Month January Year 1968

The Above well was plugged as follows:

200' of 13 3/8" surface pipe, cemented with 225 sacks. 4980' of 5 1/2" long string, cemented with 50 sacks. Plug back T.D. 4952'. Top perforation 4917'. Bottom of the hole was sanded to 4875', and cemented with 5 sacks, through the dump bailer, with cement from 4875' to 4835'. 4210' of 5 1/2" long string was recovered from the hole, Fluid level in the hole was at 208', bridge plug and rock bridge from 208' to 200', and cemented with 60 sacks, with cement from 200' to 125'. Hole was filed with mud to 30', rock bridge from 30' to 20', and cemented with 15 sacks, with cement from 20' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Annie Elving
Well Plugging SupervisorDATE 1/22/68INV. NO. 7128-4