

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
1-15-73  
JAN 15 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Raymond Oil Co Inc

Complete Address 200 W Douglas Wichita, KS

Lease Name Davis Ranch D Well No. 3

Location C SW/4 Sec. 33 Twp. 33 Rge. 14 (E)  (W) W

County Barber Total Depth 4715

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 3:00 PM Day 13 Month 1 Year 1973

The above well was plugged as follows:  
200 ft 13" surface, cement circulated. 4708 ft 4 1/2 long string  
cemented with 100 sacks. Top perf. 4629 ft. Sand to 4600 ft,  
3 sacks cement with bailer. Pulled 1800 ft 4 1/2. Set 10 ft rock  
bridge at 250 ft. Fill hole with 8 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M Russell Biberstein  
Well Plugging Supervisor

DATE 1/15/73  
INV. NO. 6848-W