

15-007-16651-0000

Form CP-3
Rev. 6-4-68

KANSAS

al
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

SEP 19 1972
9-19-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Braden-Deem Inc.

Complete Address 200 E 1st Wichita, Ks

Lease Name Wheat Well No. 4

Location NW/SE Sec. 33 Twp. 33 Rge. 14 (E) (W)

County Barber Total Depth 4830

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 11:00 AM Day 18 Month 9 Year 1972

The above well was plugged as follows:

364 ft 8 5/8 surface pipe cement circulated. 4746 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 4632 ft. Sand to 4600 ft, 5 sacks
cement with bailer. Pulled 3772 ft 5 1/2. Set 10 ft rock bridge at
350 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. Russell Bickel*
Well Plugging Supervisor

INVOICED

DATE 9/19/72

INV. NO. 6342-4