

15-007-30876 0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 30 1965  
8-30-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Lario Oil & Gas Company  
Complete Address: 301 S. Market, Wichita, Kansas  
Lease Name Margaret M. Lenkner Well No. # 1  
Location C SW Sec. 35 Twp. 33 Rge. 14 (E) (W) W  
County Barber Total Depth 4860'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: K & E Drilling, Inc.  
Address: 719 Union Center, Wichita, Kansas License No.       
Operation Completed: Hour 12:00AM Day 26th Month August Year 1965

The Above well was plugged as follows:

401' of 8 5/8" surface pipe, cement circulated with 400 sacks. Hole  
was filled with drilling mud to 300', 1st cementing plug, bridged solid  
with hulls on fluid at 300', and cemented with 25 sacks. Hole was filled  
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls  
on fluid at 40', and cemented with 10 sacks to the base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 8/30/65  
INV. NO. 1707-W