

KANSAS

SP
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 30 1973
7-30-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Specter Pipe & Supply Inc

Complete Address Box 169 Russell, KS

Lease Name Davis Ranch Unit Well No. 2

Location C NW Sec. 32 Twp. 33 Rge. 14 (E) (W)

County Barber Total Depth 4780

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 5:00 PM Day 26 Month 7 Year 1973

The above well was plugged as follows:

201 ft 13 3/8 surface cemented with 225 sacks. 4776 ft 4 1/2 long string
cemented with 125 sacks. Top perf. 4718 ft. Sand to 4700 ft, 3
sacks cement with bailer. Pulled 3700 ft 4 1/2. Set 20 ft rock bridge
at 120 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *Russell B. Buntion*
Well Plugging Supervisor

INVOICED
DATE 7-30-73
INV. NO. 7697-W