

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed February 23, 1968.

RECEIVED
STATE CORPORATION COMMISSION
3-5-68
MAR 5 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bowers Drilling Company, Inc.

Complete Address: 1434 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name Schubbach Well No. # 1

Location C N/2 SE Sec. 1 Twp. 34 Rge. 12 (E) (W) W

County Barber Total Depth 4785'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Bowers Drilling Company, Inc.

Address: 1434 Wichita Plaza Bldg., Wichita, KS. 67202 License No. _____

Operation Completed: Hour 1:00AM Day 2nd Month March Year 1968

The Above well was plugged as follows:

326' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole was
filled with drilling mud to 300', 1st cementing plug, bridged with 1/2 sack
of hulls on fluid at 300', and cemented with 25 sacks, with cement from 290'
to 215'. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks,
with cement from 30' to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/5/68
INV. NO. 7362-U

Signed: Archie Elving
Well Plugging Supervisor