

15-867-19893-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 31 1973  
7-31-73  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Specter Pipe & Supply Inc

Complete Address Box 169 Russell, KS

Lease Name Davis Ranch Unit Well No. 1

Location 50' W/ 0/NE Sec 32 Twp. 33 Rge. 14 (E) (W) W

County Barber Total Depth 4732

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 2:00 PM Day 30 Month 7 Year 1973

The above well was plugged as follows:

200 ft 13 3/8 surface cement circulate. 849 ft 8 5/8 surface cement  
circulated. 4728 ft 4 1/2 long string cemented with 125 sacks. Top  
perf. 4656 ft. Sand to 4625 ft, 3 sacks cement with bailer. Pulled  
633 ft 8 5/8. Pulled 3940 ft 4 1/2. Set 20 ft rock bridge at 120 ft.  
Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 7/31/73  
INV. NO. 7703-4