

15-007-0153-0000

Form CP-3
Rev. 6-4-68

KANSAS

P
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1973
7-13-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Specter Pipe & Supply Inc

Complete Address Box 169 Russell, KS

Lease Name Davis Ranch Unit #3 Well No. 21

Location SW/NE/SW/SW Sec. 32 Twp. 33 Rge. 14 (E) (W) W

County Barber Total Depth 4830

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 4:00 PM Day 11 Month 7 Year 1973

The above well was plugged as follows:

199 ft 13 3/8 surface cemented with 25 sacks. 4829 ft 4 1/2 long
string cemented with 125 sacks. Open hole. Sand to 4800 ft. 3 sacks
cement with bailer. Pulled 4140 ft 4 1/2. Set 20 ft rock bridge at
120 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed *M. Russell Bibeaux*
Well Plugging Supervisor

DATE 7/13/73
INV. NO. 4621-W